

	A	B	C	D	E
1	#NAME?	Maker Towers 1301- Civil works Sept 2025			
2	No.	Particular	Unit	Rate Ajay	Revised Ajay
3	1	Dismantling / Existing flooring marble	sft	25.00	25.00
4	2	Dismantling / Existing Door / Window & A/C Frame	no.	1000.00	900.00
5	3	Hacking on wall / R.C.C.	sft	30.00	30.00
6	4	P/A 1:4 Cement /river sand plaster to new wall upto 3/4" thick and curing	sft	100.00	75.00
7	5	P/A 1:4 Cement/ riversand plaster to old wall upto 1 1/2" thick and curing	sft	160.00	145.00
8		50 mm wall plaster with chemical & fibre in plaster for strength			195.00
9	15	Bonding coat for old surface to new plaster (bonding).	sft	0.00	70.00
10		P/F mesh jalli for plaster at joints			20.00
11	18	Providing / Applying Plaster Running Electric & Plumbing Jari (No cutting) in Plaster works	rft	80.00	75.00
12	20	Providing / Applying Sunanda wp waterproof or Dr.Fixit waterproofing	sft	150.00	140.00
13	21	Providing / Filling brick bat Coba 6" deep	sft	225.00	225.00
14	22	Providing / Filling brick bat coba 9" deep	sft	275.00	275.00
15		Providing / Filling brick bat coba 12" deep	sft	400.00	400.00
16	26	P/A I.P.S. to floor and curing for 24 hrs. in Sand cement	sft /rft	150.00	150.00
17	28	P/M 4" wide R.C.C. patli between wall with 6mm steel reinforcement	rft		165.00
18	29	P/M 6" thick R.C.C. lintel on door with 8mm steel reinforcement	rft		165.00
19	30	P/M 9" thick R.C.C. lintel on door with 8mm steel reinforcement	rft		1800.00
20	31	Providing / Making brick otla 4" thk. (for Wardrobe & Kitchen)	sft	145.00	145.00
21	32	Providing / Making 1:3:6 PCC 2" thk. (Concrete Coba) in sand cement	sft	145.00	145.00
22	33	Providing / Making 1:3:6 PCC 3" thk. (Concrete Coba) in sand cement	sft	175.00	175.00
23	34	Providing / Making 1:3:6 PCC 2" thk. (Concrete Coba) with I.P.S. in sand cement	sft		250.00
24	111	Material / Debris, Loading / Unloading by Lift (Qty.calculated Breaking & Making like wall, plaster, fixing marble etc.) per truck	Sft/rft		
25	#	Dismantling / Existing flooring & wall marble	sft		35
26	#	P/M 4" thick Siporex masonry wall in 1:6 cement/sand mortar including curing etc.	sft		200
27	#	P/M 6" thick Siporex masonry wall in 1:6 cement/sand mortar including curing etc.	sft		215
28	#	P/M 9" thick Siporex masonry wall in 1:6 cement/sand mortar including curing etc.	sft		375
29		Gst will be extra as per actual.			
30		final bill will be as per actual.			